

ENVIRONMENTAL MANAGEMENT AND CONSTRUCTION PLAN

STATE OF NEW YORK PUBLIC SERVICE COMMISSION
CASE NO. 08-T-1388

**Long Island Power Authority – Certificate of Environmental Compatibility and Public
Need to Install a Second 138kV Cable in the Certified Underground Conduit from the
Riverhead Substation to the Canal Substation**

*Prepared by PSEG Long Island LLC on behalf of and as agent for the Long Island Lighting
Company d/b/a LIPA*

March 2020

This page is intentionally blank.

TABLE OF CONTENTS

1.0	SITE AND PROJECT DESCRIPTION	1-1
1.1	Certified Route	1-2
1.1.1	Riverhead Substation.....	1-3
1.1.2	Canal Substation.....	1-3
1.2	Access Points.....	1-4
1.2.1	New Access Points	1-4
1.2.2	Access from Existing Ramps and Roads.....	1-4
1.3	Property Rights and Additional Permits.....	1-5
1.4	Design Criteria.....	1-6
1.5	Fulfillment of Certificate Conditions	1-9
1.5.1	Description of Route.....	1-10
1.5.2	Laws and Regulations.....	1-10
1.5.3	Environmental Management and Construction Plan.....	1-13
1.5.4	EM&CP Contents.....	1-13
1.5.5	EM&CP Process.....	1-15
1.5.6	Notices, Reports and Consultations.....	1-17
1.5.7	Environmental Supervision	1-20
1.5.8	Cultural Resources.....	1-22
1.5.9	Public Health and Safety	1-23
1.5.10	Electric and Magnetic Fields	1-23
1.5.11	Construction	1-23
1.5.12	Transportation.....	1-26
1.5.13	Maintenance	1-27
2.0	PROJECT PERSONNEL AND PROCEDURES	2-1
2.1	Personnel	2-1
2.1.1	Project Manager.....	2-1
2.1.2	Environmental Supervisor	2-1
2.1.3	Safety Manager.....	2-1
2.1.4	Construction Inspector.....	2-2
2.1.5	Environmental Monitor(s)	2-2
2.1.6	Contractor Project Manager	2-2
2.1.7	Contractor Safety Supervisor	2-3
2.2	Procedures	2-3
2.2.1	Worksite Health and Safety	2-3
2.2.2	Required Orientations.....	2-3
2.2.2.1	Site Specific Safety Orientation	2-3
2.2.2.2	Project Orientation.....	2-3
2.2.2.3	Stop Work Procedures	2-4
2.2.3	Traffic Safety	2-4
2.2.4	Vegetation Maintenance	2-4
2.2.5	Spill Prevention, Control and Countermeasures	2-5
2.2.5.1	Other Materials.....	2-7

3.0	ENVIRONMENTAL PROTECTION AND MITIGATION	3-1
3.1	Vegetation and Animal Management	3-1
3.1.1	Vegetation Management	3-1
3.1.2	Delineation of Existing Vegetation	3-2
3.1.3	Vegetation Protection	3-2
3.1.4	Plant Root Protection and Excavation Methods	3-3
3.1.5	Ground Cover Protection	3-3
3.1.6	Rare, Threatened and Endangered Species	3-3
3.1.6.1	Habitat Suitability	3-6
3.1.6.2	Northern long-eared bat (NLEB)	3-7
3.1.6.3	Tiger Salamander	3-8
3.1.6.4	RTE Best Management Practices	3-8
3.2	Water Resources	3-9
3.2.1	Surface Water Resources	3-9
3.2.2	Freshwater Wetlands	3-10
3.2.3	Groundwater and Dewatering	3-10
3.3	Sensitive Land Uses	3-11
3.4	Noise-Sensitive Areas	3-11
3.4.1	Noise Monitoring	3-12
3.5	Cultural Resources	3-13
3.6	Soil Handling and Disposal	3-13
3.7	Recreational Areas	3-13
3.8	Agricultural Areas	3-14
3.9	Hydrologic Zones for Aquifer Recharge	3-14
3.10	Critical Environmental Areas	3-14
3.10.1	Central Pine Barrens Core Preservation Area	3-14
3.10.2	Central Pine Barrens Compatible Growth Area	3-15
3.10.3	Special Groundwater Protection Area	3-15
4.0	SOIL EROSION AND SEDIMENT CONTROL	4-1
4.1	Stormwater Pollution Prevention Plan	4-2
5.0	STANDARD CONSTRUCTION PRACTICES	5-1
5.1	Construction Equipment and Methods	5-1
5.2	Pre Construction	5-1
5.3	During Construction	5-2
5.3.1	Marshalling Yards	5-3
5.4	Construction Time Restrictions	5-4
5.5	Worksite Safety	5-4
5.6	Construction Worker Parking Areas	5-4
6.0	ACCESS POINTS AND TRAFFIC CONTROL PLAN	6-1
6.1	Road Closures	6-1
6.2	NYSDOT Requirements	6-2
7.0	CLEAN-UP AND RESTORATION	7-1
7.1	Removal of Construction Materials	7-1

7.2	Removal of Vegetation.....	7-1
7.3	Restoration of Vegetation & Landscaping Plan	7-1
7.4	Plant Inspection and Maintenance.....	7-2
7.5	Paving Replacement	7-2
7.6	Routine Highway Maintenance	7-3
8.0	COMMUNITY RELATIONS.....	8-1
8.1	Public Notification.....	8-1
	8.1.1 Project Website.....	8-1
	8.1.2 Email Portal	8-1
	8.1.3 Hotline	8-1
	8.1.4 Fact Sheet	8-2
8.2	Consultation and Public Notice	8-2
	8.2.1 Public Notices.....	8-2
8.3	Complaints.....	8-3
	8.3.1 Complaint Resolution Procedures	8-3

ATTACHMENTS

- ATTACHMENT 1 – Plan and Profile Drawings
- ATTACHMENT 2 – Maintenance and Protection of Traffic Plan
- ATTACHMENT 3 – Periodic Maintenance and Inspection MPT Plan
- ATTACHMENT 4 – Vegetation Management Plan
- ATTACHMENT 5 – Stormwater Pollution Prevention Plan
- ATTACHMENT 6 – Agency Consultations
- ATTACHMENT 7 – PSEG Long Island SOP EG-706
- ATTACHMENT 8 – Supervisors Report
- ATTACHMENT 9 – EM&CP Public Notice
- ATTACHMENT 10 – Invasive Species Management Plan